

Report 11407
18 February 1998

GENCORP
AEROJET

**Integrated Advanced Microwave Sounding Unit-A
(AMSU-A)**

Engineering Test Report

**AMSU-A1 METSAT Instrument (S/N 105) Qualification
Level Vibration Tests of December 1998 (S/O 605445,
OC-419)**

**Contract No. NAS 5-32314
CDRL 207**

Submitted to:

**National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland 20771**

Submitted by:

**Aerojet
1100 West Hollyvale Street
Azusa, California 91702**

Aerojet

**Report 11407
18 February 1998**

**Integrated Advanced Microwave Sounding Unit-A
(AMSU-A)**

Engineering Test Report

**AMSU-A1 METSAT Instrument (S/N 105) Qualification
Level Vibration Tests of December 1998 (S/O 605445,
OC-419)**

**Contract No. NAS 5-32314
CDRL 207**

Submitted to:

**National Aeronautics and Space Administration
Goddard Space Flight Center
Greenbelt, Maryland 20771**

Submitted by:

**Aerojet
1100 West Hollyvale Street
Azusa, California 91702**

GENCORP AEROJET

INTEROFFICE MEMO

TO: L. T. Paliwoda **DATE:** 18-Feb-1999
a1vib-sn105.doc
FROM: R. J. Heffner 170:8411#1999#36
SUBJECT: AMSU-A1 METSAT Instrument (S/N 105) Qualification Level Vibration Tests of December 1998 (S/O 605445, OC-419)
COPIES TO: J. .A. Alvarez, D. H. Brest, D. B. Chi, D. L. Tran, Writer, File

REFERENCES:

- 1 "Advanced Microwave Sounding Unit-A1 (AMSU-A1) Instrument Assembly METSAT Qualification Level Vibration Testing", Shop Order 605445 (OC-419), July 1998.
2. "METSAT/AMSU A1 Top Assy", Dwg. 1331720.
3. "Vibration and Sine Burst Qualification and Acceptance Test Procedure for the AMSU-A System", Aerojet Process Specification AE-26151/1D, 17 September 1998.
4. "Failure Review Board (FRB) Meetings Held in Dec. 1998 and Jan. 1999 (F/AR 171)", Added Resonance (120 Hz.) after Qualification, latest printing IOM 6146/1999#2, D. Woon.
5. "Failure Review Board (FRB) Meeting Held Jan. 1999 (F/AR 178)", Channel 8 Anomaly during Thermal Cycling, 6145/1999#1, E. Lorenz.
6. "AMSU-A1 EOS Instrument (S/N 202) Qualification Level Vibration Tests of August 1998 (S/O 565632, OC-417)", 170:8411#98-604, R. J. Heffner, 10 Nov. 1998.
7. "AMSU-A1 EOS Instrument (S/N 202) Qualification Vibration Test Review, 170:8411#98-859, R. J. Heffner, 04 Dec. 1998.
8. "Test Report - AMSU-A1 Engineering Model Reflector Response Tests", Report No. 10418, February 1994.

PURPOSE

The purpose of this memo is to present a summary of the qualification level vibration testing performed on the S/N 105 AMSU-A1 Ref. 2 Instrument during the December 1998 to January 1999 time frame.

SUMMARY

The Ref. 2, S/N 105, METSAT AMSU-A1 instrument was vibration tested to qualification levels per the Ref. 3 procedure and Ref. 1 shop order. The instrument withstood the 8.8 Grms

random vibration test, and the 16.3g sine burst test in each of the three orthogonal axes. Z-axis testing (perpendicular to the sidemount) was performed first, with pre-random and post-random low level sine sweep responses showing only minor resonant frequency degradation, primarily in the reflectors. Sine burst produced no changes in response throughout the instrument.

The unit X-axis testing (perpendicular to the baseplate) produced more significant results, with pre and post-random sine sweeps identifying changes throughout the structure. Locations, such as the instrument top panel (Accel#16) experienced an 8 Hz. reduction in 1st natural frequency (129 to 121 Hz.). The upper reflector (Accel#32) and upper motor (Accel#22) saw similar response changes, (1st resonance shifting from 129 to 120 Hz.), while the lower reflector (Accel#31) and the lower motor (Accel#20), each showed an added mode at approximately 120 Hz. The sine burst test, however, produced no significant response changes. The change in the instruments' response was significant enough to be considered as a test anomaly.

After documenting the X-axis qualification level test results anomaly by a failure analysis review (F/AR 171, Ref. 4), and investigating for instrument structural changes, and finding nothing obviously wrong, it was concluded that the S/N 105 instrument had experienced a "settling in effect" by the significant X-axis loading. To insure that the instrument remained stable, with no more "settling in", an added X-axis acceptance level (workmanship) random vibration was performed. Responses before and after the workmanship random vibration, in the pre-sine and post-sine displays, showed nearly identical responses, concluding that the instrument was now stable.

The remaining axis (Y-axis, parallel to the motors' shafts) was run at qual. level and showed through the pre and post-random sine sweeps, only relatively minor changes in response level and frequency. Resonant frequencies degraded by 1 or 2%, while transmissibility's varied. The sine burst test, again in the Y-axis, produced no significant response changes.

With the S/N 105 A1 instrument considered as satisfying the qualification level vibration tests (Limited Performance Tests (LPT's) were passed after Z and X vibrations, and the more involved Comprehensive Performance Test (CPT) was passed after the concluding Y-axis vibration), the instrument was sent to Thermal Cycling Testing. In the 1st Thermal Cycle, however, the instrument displayed an inconsistency at Channel 8, as discussed in Ref. 5. Subsequent repair of the S/N 105 instrument (replacement of the Channel 8 DRO), required an added workmanship (acceptance level) random vibration test be passed.

The added workmanship test was to be an X-axis acceptance level test sequence of sine sweep, acceptance random, sine sweep. The pre-random sine sweep was completed. At that time an electrical short was noted in the instrument, further delaying the mechanical vibration testing until the shorting problem was diagnosed and repaired.

After eliminating the electrical short, the instrument was again readied for the workmanship (X-axis) test sequence of sine sweep, acceptance random, sine sweep. The workmanship vibration tests were performed without incident. Pre and post-random sine sweep response

comparisons showed adequate agreement, with insignificant frequency and transmissibility variations.

The CPT was again successfully run after completion of the 2nd added acceptance level X-axis vibration. Passing the CPT signified the successful completion of the S/N 105 A1 qualification vibration testing.

DISCUSSION

METSAT qualification level testing was begun on the S/N 105 A1 assembly during the month of December 1998, starting in the METSAT Z-axis (perpendicular to the sidemount). The vibration qualification test sequence, for each axis, per the Ref. 3 procedure was:

1. Low level sine sweep (0.25 g)
2. Full level random vibration (8.8 Grms spec.)
3. Low level sine sweep (0.25g)
4. Acceleration/sine burst (16.3 g)
5. Low level sine sweep (0.25g)

As the 1st test axis, the Z-axis testing was completed without incident on 04 December 1998. See Tables 1 & 2 for natural frequencies, calculated Q levels, and random vibration response levels. After vibration, the LPT was performed, with the instrument passing the test.

X-axis vibration testing followed on 05 December 1998. X-Axis tests produced more significant results, with changes to the structure's frequencies and transmissibility's. The sine sweeps bracketing the full qualification level (8.8 Grms) X-axis random vibration showed significant differences in responses throughout the structure. These differences warranted the issuing of a failure analysis review (F/AR 171, Ref. 4).

The post-random sine sweep identified the following changes.

- (1) A new 1st fundamental frequency is seen at accel#20X, lower motor, where the pre-random 1st f_n of 132.7 Hz. splits into the new 1st f_n of 119.2 Hz. and 132.7 Hz.
- (2) Accel#22X, upper motor, pre-random 1st and 2nd f_n of 129.0 Hz. and 140.6 Hz. modify to 120.1 Hz. and 139.6 Hz. Thus a new ~120 Hz. frequency is seen at the upper motor.
- (3) The accelerometer on the top panel, accel#26X, shows results similar to #22X, with the post random 1st f_n of 120.9 Hz. resulting from the pre-random 129.0 Hz.
- (4) The lower reflector (accel#31X) acts much like the lower motor, with post random 1st and 2nd f_n of 120.1 Hz. and 132.7 Hz. resulting from the pre-random 132.7 Hz. 1st mode.
- (5) The upper reflector (accel#32X) acts much like the upper motor, with post random 1st and 2nd f_n of 120.1 Hz. and 139.6 Hz. resulting from the pre-random 129.0 Hz. and 140.6 Hz. values.

See Tables 1 & 2 for natural frequencies, calculated Q levels, and random vibration response levels of the X-axis data. After the post-random sine sweep, the X-axis sine burst test was run,

without any change seen in the post sine burst sine sweep. After vibration, the LPT was performed, with the instrument passing the test.

In the failure analysis review (F/AR 171, Ref. 4), it was brought to light that the finite element vibration model had predicted a resonant frequency of approx. 120 Hz., as seen in the actual vibration data. Thus it was considered that the instrument, in the Z-axis qual. test, had "re-adjusted" to a state more like the vibration model, and that additional relaxation was not probable. Prove of a 'settled' instrument would come from agreement of the structures' sine sweep responses before and after an additional workmanship random vibration.

The Ref. 4 FRB, F/AR 171 plan, involved the following steps.

- (1) Verification of preload torque's of all externally mounted screws without bonded heads.
- (2) Running of a new Bode plot.
- (3) Close inspection of instrument.
- (4) Running an added workmanship (acceptance level) X-axis random vibration.
- (5) Running the qualification level Y-axis test sequence.

No significant problems were found in steps 1, 2, and 3. A 07 December 1998 low level sine sweep, performed after steps 1, 2, and 3, verified no change in response from the post sine burst sine sweep. The Y-axis test sequence (step 5) was run after the added workmanship X-axis random vibration of step 4. To insure that the instrument remained stable, with no more "settling in", the added X-axis acceptance level (workmanship) random vibration was performed on 09 December 1998. Responses before and after the workmanship random vibration, in the pre-sine and post-sine displays, showed nearly identical responses, concluding that the instrument was now stable. See Tables 1 & 2 for natural frequencies, calculated Q levels, and random vibration response levels

The Y-axis vibration tests, (parallel to the motors' shafts) were run at qual. level and were completed without incident on 10 December 1998, showing through the pre and post-random sine sweeps, only minor changes in response level and frequency. Resonant frequencies degraded by 1 or 2%, while transmissibility's varied. The sine burst test, again in the Y-axis, produced no significant response changes. See Tables 1 & 2 for natural frequencies, calculated Q levels, and random vibration response levels. After vibration, the LPT was performed, with the instrument again passing the test.

The instrument was next sent to Thermal Cycling Testing, where, in the 1st Thermal Cycle, the instrument displayed an inconsistency at Channel 8 (as discussed in Ref. 5). Subsequent repair of the S/N 105 instrument (replacement of the Channel 8 DRO) was completed. The instrument now required another (2nd) added workmanship (acceptance level) random vibration test be passed. The workmanship random vibration test was performed in the most severe, X-axis.

The 2nd added workmanship test was to be an X-axis acceptance level test sequence of sine sweep, acceptance random, sine sweep. The pre-random sine sweep was completed. At that time an electrical short was noted in the instrument, further delaying the mechanical vibration testing until the shorting problem was diagnosed and repaired.

After eliminating the electrical short, the instrument was again readied for the workmanship (X-axis) test sequence of sine sweep, acceptance random, sine sweep. Run 23 January 1999, the pre and post-random sine sweep response comparisons showed adequate agreement, with insignificant frequency and transmissibility variations. See Tables 1 & 2 for natural frequencies, calculated Q levels, and random vibration response levels for this final acceptance level X-axis vibration.

The post-workmanship vibration CPT was successfully run on 24 January 1999, after completion of the 2nd added acceptance level X-axis vibration test. With the instrument passing the CPT, it signified the successful completion of the S/N 105 A1 qualification vibration testing.

Table 1 is included to show the predicted peak 3σ loads at the motors and reflectors based on the sine sweep responses and Miles' equation, and to show comparisons with Ref. 6 tests. Note the axes' differences between METSAT and EOS. Per Ref. 3,

METSAT X	is	EOS Z
METSAT Y	is	EOS X
METSAT Z	is	EOS Y

Sample calculations of the predicted loads at full level (-0 dB) random vibration, using Miles' equation with low level sine sweep amplification factors, are shown for Accel#20X for X-axis test data, Y response;

$$\begin{aligned}
 \text{Peak } 3\sigma &= 3 \times [(\pi/2)(\text{PSD})(f_{ni})(Q)]^{1/2} \\
 &= (3) [(\pi/2) (0.072) (132) (20)]^{1/2} \\
 &= 52 \text{ g}
 \end{aligned}$$

From Table 1, the EOS comparison for same axis, same orientation response, is only 24.5 g. Note that the Ref. 6 EOS data is from the AMSU-A1 EOS Model. The EOS qualification instrument mounts via its baseplate. METSAT, like NOAA K, L, M is mounted via its sidemount. Therefore differences between Ref. 6 and the METSAT instrument are to be expected.

Table 2 is developed to identify motor and reflector responses due to random vibration, predict peak 3σ loads and compare these peak 3σ loads with Ref. 6 EOS data, and Ref. 8 calculated levels.

From the Table 2 Y-axis qualification load data, Y response, the projected maximum peak 3σ load is 142.0 g at the lower reflector (with 134.0 g predicted at the upper reflector). Ref. 6, for EOS, determined loads of 82.2 g for the lower reflector and 89.8 g for the upper reflector, per the same loading direction and response. The Ref. 8 maximum loads determined were 224.5 g at the lower reflector and 190.4 g at the upper reflector. METSAT projected loads are appreciably higher than EOS projections. METSAT projected loads, are still below Ref. 8 calculated values.

Sample calculations for the predicted peak -0 dB load for the Y-axis, Y response, using the 1/2 power point method, is shown for Accel#31X (lower reflector),

$$\text{Peak } 3\sigma = 3 \times [(165-151)(160)]^{1/2} = 142.0g \quad \text{Peak at -0dB}$$

RESULTS

Table 1 displays sine sweep data, for the motors and reflectors, for all vibration sequences. In Table 1, for each accelerometer, the 1st natural frequency and transmissibility are listed, along with the PSD level of the random vibration spectrum at f_{n1} , and the peak 3σ load (determined via Miles equation). Ref. 6 EOS loads are listed for comparison.

Table 2 tabulates random vibration data at the reflectors and motors. At each location, the -0 dB 3σ load is found, calculated using the half-power method on the response data. Loads per Ref. 6 (EOS) are also listed for comparison purposes.

As an appendix to this report, the complete list of acceleration and power spectral density (PSD) plots at all response locations, is included.

CONCLUSIONS and RECOMMENDATIONS

The Ref. 2, S/N 105, METSAT, AMSU-A1 Instrument successfully met the qualification level vibration requirements of Ref. 3. Because of an electronic component failure and an inadequate system electrical ground, the instrument saw two additional X-axis acceptance level random vibration tests. These added tests verified the instruments structural integrity.

It is recommended to accept the A1 S/N 105 instrument.



R. J. Heffner
Mechanical Design and Analysis

Table 1 AMSU -A1 METSAT Qual Level Test Data Miles' Equ w/ 1/4 g Sine Sweep

X-Axis 1st Sine Sweep (05 Dec. 98)				Random	Peak	Ref. 6*
Accel Location	Accel	1st fn	Q	PSD Level	3 σ Load	Peak 3 σ Load
Lower Motor	20X	133	6.6	0.074	30.4	12.5
	Y	132	20	0.072	52.0	24.5
	Z	131	2.4	0.071	17.7	11.1
Upper Motor	22X	129	6	0.067	27.1	20.3
	Y	140	23.2	0.088	63.6	37.7
	Z	130	7	0.069	29.8	36.7
Lower Refl	31X	133	5.9	0.074	28.7	56.5
	Y	168	20.4	0.110	73.0	83.6
	Z	132	1	0.072	9.6	32.9
Upper Refl	32X	141	9	0.090	40.2	59.8
	Y	171	16.8	0.110	66.8	94.6
	Z	130	5.2	0.069	25.6	34.6

*Ref. EOS responses per METSAT coordinate system.

Y-Axis 1st Sine Sweep (10 Dec. 98)				Random	Peak	Ref. 6*
Accel Location	Accel	1st fn	Q	PSD Level	3 σ Load	Peak 3 σ Load
Lower Motor	20X	129	12.0	0.067	38.3	22.7
	Y	128	59.4	0.065	83.8	72.2
	Z	128	4.6	0.065	23.3	13.3
Upper Motor	22X	135	5.2	0.078	27.8	30.2
	Y	134	34.3	0.076	70.3	69.9
	Z	128	2.2	0.065	16.1	18.7
Lower Refl	31X	164	52.0	0.110	115.2	74.5
	Y	163	108.9	0.110	166.1	100.5
	Z	172	32.0	0.110	92.5	52.0
Upper Refl	32X	168	26.4	0.110	83.0	53.8
	Y	168	58.9	0.110	124.0	84.5
	Z	171	13.2	0.110	59.2	44.4

*Ref. EOS responses per METSAT coordinate system.

Table 1 AMSU -A1 METSAT Qual Level Test Data Miles' Equ w/ 1/4 g Sine Sweep (Con't)

Z-Axis 1st Sine Swp (04 Dec. 98)				Random	Peak	Ref. 6*
Accel Location	Accel	1st fn	Q	PSD Level	3 σ Load	Peak 3 σ Load
Lower Motor	20X	133	1.0	0.074	11.8	39.2
	Y	134	6.0	0.076	29.4	24.3
	Z	134	1.2	0.076	13.2	13.1
Upper Motor	22X	190	2.3	0.244	38.8	22.4
	Y	144	4.1	0.097	28.4	39.0
	Z	234	8.9	0.110	56.9	50.3
Lower Refl	31X	169	6.5	0.110	41.3	55.1
	Y	170	12	0.110	56.3	67.5
	Z	178	6.8	0.110	43.4	35.5
Upper Refl	32X	188	9.0	0.110	51.3	66.6
	Y	188	12.0	0.110	59.2	101.6
	Z	189	4.8	0.110	37.6	53.8

*Ref. EOS responses per METSAT coordinate system.

X-Axis Sine Sweep (09 Dec. 98) Repeated				Random	Peak	Ref.*
Accel Location	Accel	1st fn	Q	PSD Level	3 σ Load	Peak 3 σ Load
Lower Motor	20X	133	3.8	0.074	23.0	30.4
	Y	133	17	0.074	48.7	52.0
	Z	121	1.7	0.054	12.6	17.7
Upper Motor	22X	120	3.9	0.053	18.7	27.1
	Y	140	11	0.088	43.8	63.6
	Z	120	4.4	0.053	19.8	29.8
Lower Refl	31X	168	25.8	0.110	82.1	28.7
	Y	168	40	0.110	102.2	73.0
	Z	168	8.8	0.110	47.9	9.6
Upper Refl	32X	171	10.0	0.110	51.6	40.2
	Y	171	32	0.110	92.2	66.8
	Z	183	5	0.110	37.7	25.6

*Ref. from initial X-Axis sine sweep (05 Dec. 98)

Table 1 AMSU -A1 METSAT Qual Level Test Data Miles' Equ w/ 1/4 g Sine Sweep (Con't)

X-Axis Final Sine Sweep (23 Jan. 99) Repeated				Random	Peak	Ref.*
Accel Location	Accel	1st fn	Q	PSD Level	3 σ Load	Peak 3 σ Load
Lower Motor	20X	130	4.1	0.069	22.8	23.0
	Y	130	19.2	0.069	49.3	48.7
	Z	119	1.2	0.051	10.2	12.6
Upper Motor	22X	118	5	0.050	20.4	18.7
	Y	133	16.8	0.074	48.4	43.8
	Z	120	7	0.053	25.0	19.8
Lower Refl	31X	167	18.8	0.110	69.9	82.1
	Y	167	32	0.110	91.2	102.2
	Z	175	8.4	0.110	47.8	47.9
Upper Refl	32X	166	7.3	0.110	43.4	51.6
	Y	173	14.8	0.110	63.1	92.2
	Z	120	5.2	0.053	21.6	37.7

*Ref. from previous X-Axis sine sweep (09 Dec. 98)

Table 2 AMSU-A1 METSAT Qual Level Test Data 1/2 Power Points

X-Axis Full Qualification Level (05 Dec. 98)

Accel Location	Accel	Total Grms	lin. 1st fn		1st fn		1st Res G2/Hz	1st Res Pk Grms	-0 dB Peak Load 3 σ	Ref. 6 -0 dB Pk 3 σ Load
			low	high	low	high				
Lower Motor	20X	14.1								
	Y	13.3	0.2983	0.4035	123	132	1.5	3.7	11.0	6.0
	Z	16.5								
Upper Motor	22X	12.3								
	Y	20.0	0.3553	0.4868	128	140	2.9	5.9	17.7	11.5
	Z	18.4								
Lower Refl	31X	78.0	0.6579	0.7456	158	168	4.0	6.3	19.0	
	Y	60.1	0.6316	0.7807	155	172	12	14.3	42.8	17.7
	Z	56.8	0.9649	-	195	209	0.29	2.0	6.0	
Upper Refl	32X	75.1	0.8991	-	187	205	4.7	9.2	27.6	25.7
	Y	51.6	0.6681	0.7920	159	173	16	15.0	44.9	52.8
	Z	56.9	0.7149	0.8816	164	184	0.52	3.2	9.7	

Y-Axis Full Qualification Level (10 Dec. 98)

Accel Location	Accel	Total Grms	lin. 1st fn		1st fn		1st Res G2/Hz	1st Res Pk Grms	-0 dB Peak Load 3 σ	Ref. 6 -0 dB Pk 3 σ Load
			low	high	low	high				
Lower Motor	20X	10.9								
	Y	31.3	0.2632	0.3684	120	129	29	16.2	48.5	46.5
	Z	13.6								
Upper Motor	22X	11.5								
	Y	35.1	0.3158	0.5	124	141	29	22.2	66.6	50.7
	Z	11								
Lower Refl	31X	73.7	0.5965	0.7281	151	166	37	23.6	70.7	52.5
	Y	73.1	0.5921	0.7193	151	165	160	47.3	142.0	82.2
	Z	54.3								8.7
Upper Refl	32X	84.4	0.5307	0.7456	144	168	21	22.4	67.3	78.2
	Y	72.4	0.5351	0.7281	145	166	95	44.7	134.0	89.8
	Z	48.5								16.7

Table 2 AMSU-A1 METSAT Qual Level Test Data 1/2 Power Points (Con't)

Z-Axis Full Qualification Level (04 Dec. 98)

Accel Location	Accel	Total Grms	1st fn			1st fn high	1st Res		1st Res Pk Grms	-0 dB Peak G Load	Ref. 6 -0 dB Pk 3 σ Load
			lin.	1st fn low	lin. 1st fn high		G2/Hz				
Lower Motor	20X	12.1									
	Y	22.4	0.7851	172	0.8728	183	0.42	2.1	6.4	10.9	
	Z	26.9									
Upper Motor	22X	10.4									
	Y	16.3	0.8026	174	0.9298	190	0.5	2.8	8.5	30.7	
	Z	15.2								45.3	
Lower Refl	31X	92.8								20.4	
	Y	58.5	0.6667	159	0.807	175	2.6	6.4	19.3	35.2	
	Z	82.6								6.4	
Upper Refl	32X	73.6	-	220	-	230	19	13.8	41.4	56.3	
	Y	35.7	0.693	162	0.7851	172	3.0	5.5	16.4	114.6	
	Z	52.8								33.7	


X-Axis Full Acceptance Level (09 Dec. 98)

Accel Location	Accel	Total Grms	1st fn			1st fn high	1st Res		1st Res Pk Grms	-0 dB Peak G Load	Ref. 6 -0 dB Pk 3 σ Load
			lin.	1st fn low	lin. 1st fn high		G2/Hz				
Lower Motor	20X	8.7									
	Y	8	0.3114	124	0.4342	135	1.45	4.0	12.0	3.7	
	Z	9.0									
Upper Motor	22X	6.7									
	Y	10.8	0.3947	131	0.5175	143	1.25	3.9	11.6	9.4	
	Z	10.1									
Lower Refl	31X	47.6									
	Y	29.5	0.6578	158	0.7412	167	10	9.5	28.5	19.9	
	Z	37.7									
Upper Refl	32X	44.7									
	Y	31.1	0.7061	163	0.7939	173	17	13.0	39.1	18.1	
	Z	46.1								39.1	

Table 2 AMSU-A1 METSAT Qual Level Test Data 1/2 Power Points (Con't)

X-Axis Full Acceptance Level (23 Jan. 99)												
Accel Location	Accel	Total Grms	lin. 1st fn		1st fn high	1st Res		1st Res G2/Hz	-0 dB Peak		Ref. 6	
			low	high		low	high		3 σ Load	3 σ Load	-6 dB Pk	3 σ Load
Lower Motor	20X	8.1										
	Y	8.2	0.2719	0.3991	121	132	0.85	3.1	9.2		3.7	
	Z	7.5										
Upper Motor	22X	5.5										
	Y	10	0.2018	0.4386	115	136	1.35	5.3	16.0		9.4	
	Z	8.2										
Lower Refl	31X	40										
	Y	27	0.6491	0.7456	157	168	6.2	8.3	24.8		19.9	
	Z	31.5										
Upper Refl*	32X	43.1										
	Y	20.4	0.6535	0.7851	157	172	2	5.5	16.4		18.1	
	Z	25.9									39.1	

C:\My Documents\amsua1\1a1vib-sn105-1999#36.doc
C:\My Documents\amsua1\metsata1-sn105.xls

		Report Documentation Page	
1. Report No. ---	2. Government Accession No. ---	3. Recipient's Catalog No. ---	
4. Title and Subtitle Integrated Advanced Microwave Sounding Unit-A (AMSU-A), Engineering Test Report		5. Report Date 18 February 1999	
		6. Performing Organization Code ---	
7. Author(s) R. J. Heffner		8. Performing Organization Report No. 11407	
		10. Work Unit No. ---	
9. Performing Organization Name and Address Aerojet 1100 W. Hollyvale Azusa, CA 91702		11. Contract or Grant No. NAS 5-32314	
12. Sponsoring Agency Name and Address NASA Goddard Space Flight Center Greenbelt, Maryland 20771		13. Type of Report and Period Covered Final	
		14. Sponsoring Agency Code ---	
15. Supplementary Notes ---			
16. ABSTRACT (Maximum 200 words) This is the Engineering Test Report, AMSU-A1 METSAT Instrument (S/N 105) Qualification Level Vibration Tests of December 1998 (S/O 605445, OC-419), for the Integrated Advanced Microwave Sounding Unit-A (AMSU-A).			
17. Key Words (Suggested by Author(s)) EOS Microwave System		18. Distribution Statement Unclassified --- Unlimited	
19. Security Classif. (of this report) Unclassified	20. Security Classif. (of this page) Unclassified	21. No. of pages	22. Price ---

NASA FORM 1626 OCT 86

PREPARATION OF THE REPORT DOCUMENTATION PAGE

The last page of a report facing the third cover is the Report Documentation Page, RDP. Information presented on this page is used in announcing and cataloging reports as well as preparing the cover and title page. Thus, it is important that the information be correct. Instructions for filling in each block of the form are as follows:

Block 1. Report No. NASA report series number, if preassigned.

Block 2. Government Accession No. Leave blank.

Block 3. Recipient's Catalog No. Reserved for use by each report recipient.

Block 4. Title and Subtitle. Typed in caps and lower case with dash or period separating subtitle from title.

Block 5. Report Date. Approximate month and year the report will be published.

Block 6. Performing Organization Code. Leave blank.

Block 7. Authors. Provide full names exactly as they are to appear on the title page. If applicable, the word editor should follow a name.

Block 8. Performing Organization Report No. NASA installation report control number and, if desired, the non-NASA performing organization report control number.

Block 9. Performing Organization Name and Address. Provide affiliation (NASA program office, NASA installation, or contractor name) of authors.

Block 10. Work Unit No. Provide Research and Technology Objectives and Plants (RTOP) number.

Block 11. Contract or Grant No. Provide when applicable.

Block 12. Sponsoring Agency Name and Address. National Aeronautics and Space Administration, Washington, D.C. 20546-0001. If contractor report, add NASA installation or HQ program office.

Block 13. Type of Report and Period Covered. NASA formal report series; for Contractor Report also list type (interim, final) and period covered when applicable.

Block 14. Sponsoring Agency Code. Leave blank.

Block 15. Supplementary Notes. Information not included

elsewhere: affiliation of authors if additional space is required for Block 9, notice of work sponsored by another agency, monitor of contract, information about supplements (file, data tapes, etc.) meeting site and date for presented papers, journal to which an article has been submitted, note of a report made from a thesis, appendix by author other than shown in Block 7.

Block 16. Abstract. The abstract should be informative rather than descriptive and should state the objectives of the investigation, the methods employed (e.g., simulation, experiment, or remote sensing), the results obtained, and the conclusions reached.

Block 17. Key Words. Identifying words or phrases to be used in cataloging the report.

Block 18. Distribution Statement. Indicate whether report is available to public or not. If not to be controlled, use "Unclassified-Unlimited." If controlled availability is required, list the category approved on the Document Availability Authorization Form (see NHB 2200.2, Form FF427). Also specify subject category (see "Table of Contents" in a current issue of STAR) in which report is to be distributed.

Block 19. Security Classification (of the report). Self-explanatory.

Block 20. Security Classification (of this page). Self-explanatory.

Block 21. No. of Pages. Count front matter pages beginning with iii, text pages including internal blank pages, and the RDP, but not the title page or the back of the title page.

Block 22. Price Code. If Block 18 shows "Unclassified-Unlimited," provide the NTIS price code (see "NTIS Price Schedules" in a current issue of STAR) and at the bottom of the form add either "For sale by the National Technical Information Service, Springfield, VA 22161-2171" or "For sale by the Superintendent of Documents, U.S. Government Printing Office, Washington, D.C. 20402-0001," whichever is appropriate.

GENERAL INSTRUCTIONS FOR COMPLETING SF 298

The Report Documentation Page (RDP) is used in announcing and cataloging reports. It is important that this information be consistent with the rest of the report, particularly the cover and title page. Instructions for filing in each block of the form follow. It is important to stay within the lines to meet optical scanning requirements.

Block 1. Agency Use Only (Leave blank)

Block 2. Report Date Full publication date including day, month, and year, if available (e.g., 1 Jan 88). Must cite at least the year.

Block 3. Type of Report and Dates Covered State whether report is interim, final, etc. If applicable, enter inclusive report dates (e.g., 10 Jun 87 - 30 Jun 88).

Block 4. Title and Subtitle A title is taken from the part of the report that provides the most meaningful and complete information. When a report is prepared in more than one volume report the primary title, add volume number and include subtitle for the specific volume. On classified documents enter the title classification in parentheses.

Block 5. Funding Numbers To include contract and grant numbers; may include program element number(s), project number(s), task number(s), and work unit number(s). Use the following labels:

C	-	Contract	PR	-	Project
G	-	Grant	TA	-	Task
PE	-	Program Element	WU	-	Work Unit Accession No.

Block 6. Author(s) Name(s) of person(s) responsible for writing the report, performing the research, or credited with the content of the report. If editor or compiler, this should follow the name(s).

Block 7. Performing Organization Name(s) and Address(es) Self-explanatory.

Block 8. Performing Organization Report Number Enter the unique alphanumeric report number(s) assigned by the organization performing the report.

Block 9. Sponsoring/Monitoring Agency Name(s) and Address(es) Self-explanatory.

Block 10. Sponsoring/Monitoring Agency Reports Number (if known).

Block 11. Supplementary Notes Enter information not included elsewhere such as: Prepared in cooperation with ...; Trans. of ...; To be published in ... When a report is revised, include a statement whether the new report supersedes or supplements the older report.

Block 12.a Distribution/Availability Statement Denotes public availability or limitations. Cite any availability to the public. Enter additional limitations or special markings in all capitals (e.g., NOFORN, REL, ITAR).

DOD - See DoDD 5230.24 *Distribution Statement on Technical Documents*

DOE - See authorities.

NASA - See Handbook NHB 2200.2.

NTIS - Leave blank.

Block 12.b Distribution Code

DOD - Leave blank.

DOE - Enter DOE distribution categories from the standard Distribution for Unclassified Scientific and Technical Reports.

NASA - Leave blank.

NTIS - Leave blank.

Block 13. Abstract Include a brief *Maximum 200 words* factual summary of the most significant information contained in the report.

Block 14. Subject Terms Keywords or phrases identifying major subjects in the report.

Block 15. Number of Pages Enter the total number of pages.

Block 16. Price Code Enter appropriate price code (7TS only).

Block 17 - 19. Security Classifications Self-explanatory. Enter U.S. Security Classification in accordance with U.S. Security Regulations (i.e., UNCLASSIFIED). If form contains classified information, stamp classification on the top and bottom of the page.

Block 20. Limitation of Abstract This block must be completed to assign a limitation to the abstract. Enter either UL (unlimited) or SAR (same as report). An entry in this block is necessary if the abstract is to be limited. If blank, the abstract is assumed to be unlimited.



DOCUMENT APPROVAL SHEET

TITLE <u>Engineering Test Report</u> AMSU-A1 METSAT Instrument (S/N 105) Qualification Level Vibration Tests of December 1998 (S/O 605445, OC-419)		DOCUMENT NO. Report 11407 18 February 1999	
INPUT FROM: R. J. Heffner	CDRL: 207	SPECIFICATION ENGINEER: N/A	DATE
CHECKED BY: N/A	DATE	JOB NUMBER: N/A	DATE
APPROVED SIGNATURES		DEPT. NO.	DATE
Product Team Leader (L. Paliwoda) <u><i>L. Paliwoda</i></u>		7888	2/25/99
Systems Engineer (R. Platt) <u><i>R. Platt</i></u>		8341	3/1/99
Design Assurance (E. Lorenz) <u><i>E. Lorenz</i></u>		8331	3/2/99
Quality Assurance (R. Taylor) <u><i>R. Taylor</i></u> For		7831	3/1/99
Technical Director/PMO (P. Patel) <u><i>P. Patel</i></u>		8341	3/2/99
Released: Configuration Management (J. Cavanaugh) <u><i>J. Cavanaugh</i></u>		8361	3/2/99
By my signature, I certify the above document has been reviewed by me and concurs with the technical requirements related to my area of responsibility.			
(Data Center) FINAL			
Please return this sheet and the reproducible master to Jim Kirk (Bldg. 1/Dept. 8631), ext. 2081.			

REPORT DOCUMENTATION PAGE

Form Approved

OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE February 1999	3. REPORT TYPE AND DATES COVERED Contractor Report	
4. TITLE AND SUBTITLE Integrated Advanced Microwave Sounding Unit-A (AMSU-A), Engineering Test Report			5. FUNDING NUMBERS NAS5-32314	
6. AUTHOR(S) R. J. Heffner				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS (ES) Aerojet 1100 W. Hollyvale Azusa, CA 91702			8. PERFORMING ORGANIZATION REPORT NUMBER 11407 18 February 1999	
9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS (ES) National Aeronautics and Space Administration Washington, DC 20546-0001			10. SPONSORING / MONITORING AGENCY REPORT NUMBER NASA/CR-1999-209498	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION / AVAILABILITY STATEMENT Unclassified-Unlimited Subject Category: 18 Report available from the NASA Center for Aerospace Information, 7121 Standard Drive, Hanover, MD 21076-1320. (301) 621-0390.			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) This is the Engineering Test Report, AMSU-A1 METSAT Instrument (S/N 105) Qualification Level Vibration Tests of December 1998 (S/O 605445, OC-419), for the Integrated Advanced Microwave Sounding Unit-A (AMSU-A).				
14. SUBJECT TERMS EOS, Microwave System			15. NUMBER OF PAGES 12	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT Unclassified	18. SECURITY CLASSIFICATION OF THIS PAGE Unclassified	19. SECURITY CLASSIFICATION OF ABSTRACT Unclassified	20. LIMITATION OF ABSTRACT UL	